

McLEOD 234 INCLUSIONS

FEES, LEVIES & INSURANCES: By Builder
CERTIFICATES: Engineers certificate for footing and slab
FOUNDATIONS: Engineered raft slab for "M" Site
TERMITE CONTROL: Primary building elements
SOIL TEST: By Owner
COUNCIL APPLICATIONS FEES: By Builder
ELECTRICITY/TELEPHONE: Underground up to 10m by Builder, owner to pay for connection & power during construction.
CONCRETE PUMP: Concrete pump to pour concrete slab and bond beam
EXTERIOR WALLS: 200mm concrete masonry block 2.6m high ceilings
FINISH TO EXTERIOR WALLS: 2 coats of cement Quickwall render to outside of dwelling
INTERIOR WALLS: 70mm x 35mm MGP 10 @ 450mm centres, timber frame "Termite Treated"
FINISH TO INTERNAL WALLS: Plasterboard lined with painted pine skirtings 66mm x 11mm & architraves 42mm x 11mm bull nose
ROOF STYLE: All hip construction with 600mm eaves
ROOF SHEETING: COLORBOND Custom Orb
GUTTER, FASCIA, BARGE: COLORBOND square line gutter
TRUSSES: 20 Degrees: Pre-fabricated pine roof trusses @ 900mm centres H2, on steel battens
PATIO, CARPORT LINING: W R plasterboard with 90mm cornice
GABLES: 4.5mm fibre cement sheeting
EAVES: 600mm level soffits 4.5mm fibre cement sheeting
GABLE & ROOF FEATURE TRIM: Nil
ROOF INSULATION: 70mm Anticon insulation blanket to entire roof
DOWN-PIPES: Round PVC 90mm to suite 800m2 block
RAINWATER DISPOSAL: To meet local government requirements
WASTE DISPOSAL: To council sewer to max 18 lineal metres
OUTSIDE TAPS: 2 brass taps
CEILING LINING: Plasterboard on steel battens
CORNICE: 90mm cornice
WINDOW REVEALS: Four sided gyprock reveals
WINDOWS & SLIDING GLASS: Glazing – tinted obscure to bathrooms and WC
S/G DOORS: Glazing – Tinted glass to all other windows and SGD's. Powder coated aluminium frame, owner's choice of colours
FLY SCREENS: Allowed to all windows & sliding glass doors (excludes all hinged doors)
ENTRY DOOR: Choice of entrance door from Hume Newington range
ENTRY DOOR LOCK: Nexion Lockwood lock (keyed alike)
INTERNAL DOORS: 2040mm x 820mm Redicote doors
INTERNAL DOOR FRAME: Timber frame "Termite Treated"
INT. DOOR HANDLES: S/S Lockwood Symmetry Lever Series
INT. DOOR STOPS: Lemar S/S Magnetic
HOT WATER SERVICE: Dux ProFlow250 electric hot water unit
KITCHEN SINK: 1200mm Lakeland double bowl S/S inset sink & S/S drainer
LAUNDRY CUPBOARD: Laundry cupboard unit as per plan – 45L Nucleam Supreme Cabinet
VANITIES: PC \$600 (supply) each including plug & waste. Owner/s choice of design & colour
BATH TUB: Caroma Maxton bath tub white 1675mm
TAPWARE & ACCESSORIES: Kitchen sink: Caroma Quatro sink mixer. **Bathroom/Ensuite:** Caroma Quatro bath mixer, bath spout, shower mixer, shower rose/arm, basin mixer, toilet roll holders & double towel rails. **Laundry:** Brasshards Aquamix
WC SUITE: Caroma Profile II Smart Flush toilets - white (BTW toilets extra)
SHOWER/BATH SCREENS: Framed, clear laminated fixed glass screen & pivot/sliding door as per plans
MIRRORS TO VANITIES: As per plan: aluminium silver surround to suit vanity size
SITE EARTH WORKS: Not included
DRIVEWAY: 70m2 exposed aggregate concrete
GARAGE DOOR: Standard panel lift garage door with auto control & 3 handsets. Size as per plan (Wood look alike finish EXTRA COST)

All illustrations and plans are a guide & does not form any part of the final contract & may change without notice. Tropic Coast Homes retains the right to vary price without notice.

PRICE VALID AS AT 1ST OCTOBER 2021

STARTING PRICE - \$324,000

ELECTRICAL: Maximum of 10 meters Single Phase power to house

Smoke detectors as per BCA	6
Double power points	20
TV points	2
Phone points	2
Cook top Point	1
Wall oven point	1
Fans 1200mm three blades - white	8
Down lights fluoro white	10
Round fluoro	10
Booster switch solar unit	0
Wire and fit auto control garage door	1
External weather proof power point	1
External spot lights	1

KITCHEN APPLIANCES:

SMEG 60cm Appliance Pack includes: 60cm Oven, Cook top, Range hood, Dishwasher; or **PC \$2,800** for appliances of choice.

PAINTING: 1 x exterior undercoat, 2 x coats acrylic semi-gloss to walls. 1x interior undercoat. 2 x interior coats acrylic sheen to walls - 1 colour, gloss coat to internal doors skirtings, sills and architraves - 1 colour. Feature walls & staining not included.

TILES AND TILING: Tile allowance \$27m2 incl. GST (supply)

Main Bathroom – Walls

Maximum 2000mm high overall to shower

Maximum 600mm high overall to bathtub

Ensuite Bathroom Walls

Maximum 2000mm high overall to shower

Laundry Skirting

Maximum one row of tiles skirting to laundry

Laundry Splashback

Maximum 300mm high overall to tub

Kitchen Splashback

Maximum 600mm high overall to cupboards

Max tile size 450mm x 450mm ceramic tiles. Bathroom floor max. size 300mm x 300mm. All tiling to be laid square, no patterns or feature tiles allowed for.

No Porcelain tiles allowed for (extra laying fees apply).

FLOOR COVERINGS: Tiling through living areas, patio & porch **PC \$27m2 (supply)**. Carpet to all bedrooms **PC \$46/m2 (supply)**. Garage floor is plain concrete finish.

KITCHEN CABINETS: Allowance included for all cabinetry to give you flexibility to design your own kitchen to suite your living requirements
PC \$11,000.00 incl. GST

LINEN CUPBOARD: Linen cupboard with hinged door & 4 levels of laminated shelves

ROBES: Sliding vinyl doors with 1 shelf and hanging rail to all bedrooms

W.I.R ENSUITE: Walk in robe with 1 x nest of 4 levels of laminated shelves, top shelf and single hanging rail.

NB

1. Unless otherwise specified, a 6.6m setback from front boundary to wall applies.
2. No allowance has been made for possible variations arising from:
A) Special Council or other Public Authority requirements.
B) The discovery of rock, or any unsuitable soil conditions not apparent before the works commence.
C) Any unsatisfactory site or soil conditions that may not be made apparent by a soil test before the works commence.
The specifications for footings assume an "M" soil test result unless otherwise specified.
3. Specification does not allow for any earthworks or site preparation.
4. Clear access for all necessary machinery and delivery vehicles is assumed and is the responsibility of the owner. This specification is based on clear site, with no obstacles, tall grass or trees.
5. Any earthworks price is based on site preparation of cutting and filling unless specifically stated otherwise. The price does not cover retaining walls, site drainage, or any special requirements relating to earthworks in Australian Standard A.S 2870.1 or special requirements of the Environmental Act.
6. Specification is based on all survey pegs being in place & Visible.
7. If underground power is applicable, allowance is made for a maximum trench length of 10m. Any extension occasioned by meter positioning or an extra setback will be charged as an extra. Owner to pay for power during construction.
8. No allowance for rain water tank or dual reticulation of water.
9. The Builder reserves the right to change or substitute items in this schedule.
10. This schedule does not form any part of the final contract.

PRICE IS BASED ON HOME BUILD BEING WITHIN A 12KM RADIUS FROM MAREEBA OR ATHONTON. EXTRA SURCHARGE APPLIES IF FURTHER THEN 12KM.